

HSCC/BU-II/PCT /2011

Date: - 09.05.2011

**ALL BIDDERS**

**Amendment-1**

**Subject: Construction of Pre Clinical Teaching Block (02 basement + Ground + 08) for AIIMS within AIIMS campus, Ansari Nagar, New Delhi**

Dear Sir,

This has reference to the subject project, as directed,

The following AMMENDMENT-1/CLARIFICATION-1 may be noted, which shall be treated as a part of the contract to be submitted duly signed & stamp along with tender:

1. In Bill of Quantity ( Volume-V) Item no 7.05 the quantity may be read as “**2035 SQM**” in place of “4070 SQM” ( copy enclosed at Annexure-I ).
2. Please find enclosed Annexure-I added two items of BOQ (VOL-V) pertaining to Civil item no: 10.10 and 10.11 to be submitted along with BOQ duly quoted, signed and stamped.

Other conditions of tender shall remain unchanged.

Thanking you,

Yours faithfully,

(V.V.Govinda Rao)  
GM (Civil)

**Project Name: P.C.Teaching Block,AIIMS,NewDelhi.****Bill Of Quantity**

Ammendment-1

Annexure-I

Item No.	Description of Item	Qty	Unit	Rate in figures (in Rs. )	Rate in words (in Rs. )	Amount in figurs (in Rs.)
10.10	Stone work ( machine cut edges) for wall lining upto 10 m height etc. backing filled with a grout of 12mm thick cement mortar 1:3 (1 Cement : 3 coarse sand) and jointed with Cement mortar 1:2 (1 cement : 2 stone dust) including rubbing and polishing complete. (To be secured to the backing by means of cramps which shall be paid for separately)					
a)	Gwalior sand stone slabs exposed face dressed and rubbed.					
i)	30 mm thick.	1000.00	Sqm			
10.11	Providing and fixing adjustable stainless steel cramps of approved quality and of required shape and size adjustable with stainless steel nuts bolts and washer (total weight not less than 260 gms) for dry stone cladding fixed on frame work- at suitable location including making necessary recesses in stone slab, drilling required holes etc complete as per direction of the Engineer-in-charge.	2000.00	Each			