

**ALL INDIA INSTITUTE OF MEDICAL SCIENCES,  
ANSARI NAGAR, NEW DELHI**

**Dated: 26.05.2016**

**AMENDMENT No. – III**

**Project Name: Tender for “Construction of New Paid Ward Including Associated Works, Operation & Maintenance during defect liability period in AIIMS Campus, Ansari Nagar, New Delhi for AIIMS, New Delhi”.**

**Tender No. HSCC/AIIMS/NPW/2016, dated: 25.04.2016**

This has reference to subject work, the following Amendment may be noted, which shall be treated as a part of the contract to be uploaded along with tender/ bid:

**1) The Last date of submission & opening of bids has been extended as follows:**

Last date to fill/upload the tender : upto **14:30 hrs. on 31.05.2016**  
through e-Tendering

Date of Opening of bids : on 31.05.2016 at 15:00 hrs.

**2) Refer Vol.-V (BOQ) – (Civil work), the following items description has been amended as follows:**

<b>Item No.</b>	<b>Item as per BOQ</b>	<b>Amended Item</b>
<b>1.06,</b> Page No.- C-2	Designing, providing, installing temporary removable earth retaining structure (for 3-level basement as per drawing) using steel sheet piles/ soldier piles/ H beams with waller beams, hard wood wooden lagging of desired thickness, MS clamps or other suitable arrangement etc, strutting, shoring or using anchors for all lead, lift and depth including boring holes for soldier piles/ strutting structural members up to required depths and dia & filling holes as per approved structural designs & drawing to required depth. The soldier piles shall be embedded below foundation level as per	Designing, providing, installing temporary removable earth retaining structure (for 3-level basement as per drawing) using steel sheet piles/ soldier piles/ H beams with waller beams, hard wood wooden lagging of desired thickness, MS clamps or other suitable arrangement etc, strutting, shoring or using anchors for all lead, lift and depth including boring holes for soldier piles/ strutting structural members up to required depths and dia & filling holes as per approved structural designs & drawing to required depth. The soldier piles shall be embedded

	<p>approved earth retaining structure design/ drawing to required depth, conforming to relevant BIS codes and other relevant upto date specifications. The temporary earth retaining structure shall be taken out after completion of raft top and shall remain embedded permanently. The work shall be carried out strictly as per approved temporary earth retaining structure design, drawings and in coordination with other structural, architectural drawings, particular specifications and as per direction of Engineer in charge. The rate shall be inclusive of all machineries, equipment tools, tackles, design, re-design drawings, operations and other incidentals to the item of work complete. (The rate includes the cost of all materials, labour, designing of soldier piles or other structure and its vetting by IIT Delhi or other agency approved by Engineer in Charge/Client and salvage value of materials taken out after completion of the work)</p>	<p>below foundation level as per approved earth retaining structure design/ drawing to required depth, conforming to relevant BIS codes and other relevant upto date specifications. The temporary earth retaining structure shall be taken out after completion of raft top. The work shall be carried out strictly as per approved temporary earth retaining structure design, drawings and in coordination with other structural, architectural drawings, particular specifications and as per direction of Engineer in charge. The rate shall be inclusive of all machineries, equipment tools, tackles, design, re-design drawings, operations and other incidentals to the item of work complete. (The rate includes the cost of all materials, labour, designing of soldier piles or other structure and its vetting by IIT Delhi or other agency approved by Engineer in Charge/Client and salvage value of materials taken out after completion of the work)</p>
<b>3.06,</b> Page No.- C-6	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete upto plinth level.	Steel reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete at all levels.
(a)	Thermo-Mechanically Treated bars	Thermo-Mechanically Treated bars
<b>7.04,</b> Page No.- C-18	Providing and fixing machine cut, mirror / eggshell polished , Marble stone work for wall lining (veneer work) including dado, skirting, risers of steps etc., in required design and pattern wherever required, stones of different finished surface texture, on 12 mm (average) thick cement mortar 1:3 (1 cement : 3 coarse sand) laid and jointed with white cement slurry @ 3.3 kg/sqm including pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing, polishing etc. all complete as per Architectural drawings, and as directed by the Engineer-in-Charge.	Providing and fixing machine cut, mirror / eggshell polished , Marble stone work for wall lining (veneer work) including dado, skirting, risers of steps etc., in required design and pattern wherever required, stones of different finished surface texture, on 12 mm (average) thick cement mortar 1:3 (1 cement : 3 coarse sand) laid and jointed with white cement slurry @ 3.3 kg/sqm including pointing with white cement slurry admixed with pigment of matching shade, including rubbing, curing, polishing etc. all complete as per Architectural drawings, and as directed by the Engineer-in-Charge.
(a)	Flamed/polished finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.	18 mm thick Flamed/polished finish granite stone slab Jet Black, Cherry Red, Elite Brown, Cat Eye or equivalent.

- 3) The Validity of Bid Security/ EMD in the form of Bank Guarantee (BG) will be considered from the original due date of bid submission i.e. **20.05.2016**.

All other terms & Conditions of the Tender shall remain unchanged.

Prospective bidders are advised to regularly scan through HSCC e-tender portal <http://www.tenderwizard.com/HSCC> as corrigendum/amendments etc., if any, will be notified on this portal only and separate advertisement will not be made for this.

(- Sd -)

Chief General Manager (PG-II),  
HSCC (India) Ltd.  
For & on Behalf of Director, AIIMS, New Delhi