

Construction of Hostel Blocks 1, 2 and 3 at AIIMS, New Delhi					
Bill of Quantities				Annexure-IV	
New Item for CIVIL works					
Item No	Description Of Item	Qty	Unit	Rate in figures ( in Rs. )	Rate in words ( in Rs. )
3.08	Providing and laying in position machine batched, machine mixed and machine vibrated design mix cement concrete of specified grade for reinforced cement concrete work including pumping of concrete to site of laying but excluding the cost of centering, shuttering, finishing and reinforcement. including Admixtures in recommended proportions as per IS 9103 to accelerate, retard setting of concrete, improve workability without impairing strength and durability as per direction of Engineer-in-charge. M-25 grade reinforced cement concrete by using 410kg. of cement per cum of concrete. All work up to floor V level.	15000	Cum		
New Item for PHE ( Plumbing) works					
9.04	Providing and fixing Chlorinated Polyvinyl Chloride (CPVC) pipes, having thermal stability for hot & cold water supply including all CPVC plain & brass threaded fittings i/c fixing the pipe with clamps at 1.00 m spacing. This includes jointing of pipes & fittings with one step CPVC solvent cement and the cost of cutting chases and making good the same including testing of joints complete as per direction of Engineer in Charge.				
	Concealed work including cutting chases and making good the walls etc.				
(b)	20 mm nominal outer dia pipes(SDR-11)	100	Metre		
	<b>Total</b>				